

# Hallucination Case Study

## Assignment 3 — Smart Water Lab

Mahmudul Hasan (4125999049)

2026

### 1 AI claim

During test design (Week 8 Session A, Cursor Agent): “For CN=95 and rainfall  $P = 5$  mm, runoff is always zero because high CN means no runoff for small storms.”

### 2 Why this is wrong

SCS-CN initial abstraction:  $I_a = 0.2 \times (25400/\text{CN} - 254)$ .

For CN=95:  $I_a \approx 5.37$  mm, so  $P = 5$  mm gives  $Q = 0$  *by arithmetic*, not by a general rule. High CN *lowers*  $I_a$ ; small storms can still produce runoff when  $P > I_a$ .

### 3 Tests created

tests/test\_runoff.py: test\_runoff\_below\_initial\_abstraction, test\_runoff\_not\_exceed\_rainfall\_high  
src/validation.py: validate\_runoff\_mm enforces  $Q \leq P$ .

### 4 Failure discovered

Draft documentation over-generalized one (CN,  $P$ ) pair. pytest + Ia table showed the verbal rule was misleading for test design.

### 5 Fix applied

- Zero-runoff test:  $P = 2$  mm, CN=80 ( $I_a \approx 20.3$  mm).
- Physical sweep: CN = 60, 80, 95 at  $P = 100$  mm with  $Q \leq P$  assert.
- Documented in prompt\_log.md and Week 8A lab report.

### 6 Evidence checklist

| Step               | Location                           |
|--------------------|------------------------------------|
| AI prompt          | prompt_log.md Week 8A              |
| Tests              | tests/test_runoff.py               |
| Failure documented | This file + Week 8A PDF            |
| Fix                | Corrected tests + validation layer |
| Run                | pytest -q $\rightarrow$ 29 passed  |